



December 8, 2014

Second deployment for Nova Scotia's Modular Panel Bridge

Having purchased an Algonquin Modular Bridge System from Algonquin Bridge just a few years ago, the Nova Scotia Department of Transportation and Infrastructure Renewal has already redeployed the system for a second major project detour.

The Algonquin unit is now in place along a busy stretch of the Trans-Canada Highway (104) at Heatherton, near Antigonish. This bridge will help to mitigate inconvenience and delays for motorists.

For greater safety, the new permanent bridge will be set at a grade that is 5 m higher than the old bridge. The detour bridge was also set at that higher grade and, after disassembly, its approaches will be left in place for use in future highway twinning.



Project at a glance:

Project Name: Heatherton By-Pass Detour Bridge

Location: Trans-Canada Highway 104,
Heatherton, Nova Scotia

Owner: Nova Scotia Department of Transportation
and Infrastructure Renewal

Contractor: Nova Construction / Ian Sinclair
Contracting

Product: Algonquin Modular Panel Bridge

Application: Temporary Detour, Stream Crossing

Dimensions: 61 m clear span x 8.05 m width

Installation Time: Approximately one month

See all Project Profiles on
algonquinbridge.com

Algonquin Bridge
121 Gerald Parkway
Thorndale, ON N0M 2P0
1-226-213-4707
algonquinbridge.com